SPECIAL DIVISION, MYSORE.

Notice dated 27th November 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Special Division, Mysore, up to Saturday the 19th December 1931, till 12 noon for constructing two wings to the Administrative Block at P. K. T. Sanatorium, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1932.

2. The detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5. P.M. on the working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred only (Rs. 500) in cash as earnest money, and be superscribed "Tender for constructing two wings to the Administrative Block at P. K. T. Sanatorium at Mysore" in default of which, tenders will be rejected

5. The final acceptance of the tender will rest with the Superintending Engineer, Mysore Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No tender stating "percentage less than the lowest tender or as per estimated rates" will be accepted.

10. Once the tender has been accepted no claim for any concessions or higher rates will be entertained.

11. The work should be executed as per specification to be given by the Executive Engineer, Special Division.

12. The decision of the Chief Engineer in all matters, regarding measurements, rates, etc., shall be final and legally binding.

13. The rates tendered should include all incidental charges for water, electric power, scaffolding, etc.

Abstract estimate of cost for adding two wings to the Administrative Block at Princess Krishnajammanni Tuberculosis Sanatorium, Mysore.

Serial No.	Items of works	Units	Quantity	Rate	
				in figures	in words
				Rs.a.p.	
1	Dismantling the roof, floor, walls, etc., of the existing corner verandah walls for insertion of doors and windows in existing walls and blocking up gaps of bags and other patch works at junction of old and new works.	Lump sum			
2	Earthwork excavating foundation and filling in basement.	C.yds.	171		
3	Broken quartz stone jelly concrete in chunam mortar (1:2) size of jelly 1½" to 2".	C.ft.	1,359		
4	Size stone in chunam mortar foundation and basement.	„	4,102		
5	Burnt brick in mortar in Superstructure ...	„	6,278		
6	Burnt stone slabs 5" to 6" thick roughly dressed and fixed in mortar.	S.ft.	765		
7	Two line dressing for slabs	„	468		
8	Arch work burnt brick in mortar including centerings.	C.ft.	142		
9	Fixing old burnt stone slabs	S.ft.	76		

Serial No.	Items of works	Units	Quantity	Rates	
				In figures	In words
				Rs.a.p.	
10	Pillars of wire cut bricks in chunam mortar having 2 bond stones with dressed stone base and capital 6" thick including dressing and plastered, etc., complete size of pillars 1 1/8 x 1 1/8 x 8½ as per design during execution.	Each	10		
11	Removing and refixing old windows with fan and lights complete with necessary repairs and fittings.	„	4		
12	Providing and fixing new 1¾" thick teakwood doors 4½' x 8½ size one-third panelled and two-thirds glazed with ground glass shutters and 4" x 5" section frame with 4 iron clamps bolts fixed and tarred alround facing walls including hinges, hooks or wooden stoppers and all other iron fittings, etc., complete.	S.ft.	306		
13	Providing and fixing new 1¾" thick teakwood doors (4½' x 8½') fully panelled shutters 4" x 5" section frame with 4 iron clamps, bolts fixed and tarred alround facing to walls including hinges, hooks or wooden stoppers, and all other iron fittings, etc., complete.	„	114·75		
14	Providing and fixing new 1½" thick teakwood windows fully glazed with ground glasses shutters 3½" x 4½" section frame ¾" diameter iron bars 3½" apart, 6" iron hooks, end-eyes or wooden stoppers and 4 iron 1½" rings with 4 iron clamps and other fittings complete as per doors as per design during execution.	„	159.5		
15	Providing and fixing new 1½" thick teakwood windows fully glazed, inside with coloured glasses, outside panelled shutters with 4" x 5" frame including ¾" iron bars, 4 clamps central flat bar 2" x ¼" and all other iron fittings, etc., complete as per above windows	„	33		
16	Providing and fixing new 1½" teakwood windows with glazed sliding shutters 4" x 5" section frame, 4 iron clamps and other all Brass fittings as per details above.	„	77		
17	Providing and fixing new teakwood rectangular ventilators with glazed shutters and necessary fittings, etc., complete.	„	54		
18	Providing and fixing semi circular fan lights glazed over new windows with frame, etc., as per existing design.	„	20		
19	New teakwood wrought and put up ...	C.ft.	18·75		
20	Carting old rafters got from dismantling transformer House and stacked in Krishnarajendra Hospital compound and fixing.	„	34·80		
21	Carting old roofing Mangalore tiles from Krishnarajendra Hospital compound and laying them on roof after rubbing, cleaning and colouring.	Sqr.	8·64		
22	Carting old ridge tiles from Krishnarajendra Hospital and set in mortar complete.	R.ft.	79		
23	Jack arch terrace one course brick on edge and one course brick flat and haunches filled in with surki in mortar and 4" at ridge and 2" at ends of surki with quick lime concrete platered smooth at top and bottom inside, etc., complete including 3 courses of flat tiles.	Sqr.	20·10		
24	Kadapa slab wall plates on mortar bed below joists.	„	2·88		

Serial No.	Items of work	Units	Quantity	Rate	
				in figures	in words
				Rs.	
25	British standard or Tatas rolled steel girders and joists with anticorrosive paint for portions resting in walls and hoisting and grey painted the other portions two coats.	Cwts.	112·25		
26	Plain parapet wall including plastering as per design 9" x 6" base 4½" and 2' high.	R.ft.	208		
27	Plain Bond cornice 2" x 6"	„	251		
28	Cornice 9"	„	184		
29	Milk white glazed tile dadoo fixed in cement mortar (1 : 2) complete with in and out corners, borders etc., and pointed with plaster of paris :—Parapet brand or any other approved brand to be used.	Sqr.	5·30		
30	Flooring with ¾" Italian marble tiles on 3" overlying lime concrete bed laid on cement mortar and pointed with plaster of paris, etc., complete.	„	3·50		
31	Botany cement concrete flooring 1, 2, 4 proportion 1½" thick on existing concrete with asphalt expansion joints, etc., complete including cement plastering at top.	„	19·85		
32	Cement concrete cills for windows with cement plaster.	„	45		
33	Shell lime plastering smooth three coats as per specification of Lalithamahal.	„	13·75		
34	Chunam plastering	„	71·27		
35	Chunam pointing	„	7·10		
36	White-washing two coats	„	68·01		
37	Carting old available eave board from Krishnarajendra Hospital compound and putting them as per existing pattern with two coats of chocolate paint.	R.ft.	72		
38	Japan painting two coats	Sqr.	13·66		
39	Silicate silver grey or zinc white paint two coats.	„	10·72		
40	Boxing girders including plastering complete...	R.ft.	161		
41	Tie or distant rods, threads including bolts and nuts complete for jack arch terrace.	Lbs.	100		
42	Pedimental Parapet as per design ...	Each	4		
43	Front bay decoration including necessary brick work, rear arch, mortar panels, cornice, etc., complete as per existing design.	„	2		
44	False bay work at sides to match with front decoration including 2¼" projection of brick work, etc., complete.	„	2		
45	Rounding corners and basement cornice ..	L. S.	...		
46	Providing and fixing ornamental finial ...	Each	2		
47	Providing a counter in the compounding room.	„	1		

V. V. PATANKAR
Executive Engineer.